



बामर लॉरी एण्ड कं. लिमिटेड
(बामर लॉरी एण्ड कं. लिमिटेड)
Balmer Lawrie & Co Ltd
(A Government of India Enterprise)

Balmer Lawrie & Co Ltd
(A Government of India Enterprise)
Administration Department
21, Netaji Subhas Road
Kolkata - 700 001

TENDER

FOR

"Construction of Waste Disposal Room"

At

Head Office, 21, N S Road, Kolkata – 700 001

TENDER REFERENCE – ADMIN/12

TENDER NO: - 07/2018-2019 DATED 22.06.2018

DUE ON 26.06.2018 BY 3.00 PM

NOTICE INVITING TENDER
NIT No – 07/2018-19, Dated – 22.06.2018
DUE ON 326.06.2018 BY 3.00 PM

Tender No. 07/2018-19

Dated: 22/06/2018

“Construction of Waste Disposal Room”

Balmer Lawrie & Co. Ltd. (BL) is a Mini-Ratna-I Public Sector Enterprise, under the Ministry of Petroleum & Natural Gas, Government of India. Along with its five Joint Ventures in India and abroad, it is a much-respected transnational diversified conglomerate with presence in both manufacturing and service sectors. Balmer Lawrie is a market leader in Steel Barrels, Industrial Greases & Specialty Lubricants, Corporate Travel and Logistics Services.

1.0 Tenders are invited from **Enlisted/Registered Vendors only** with Balmer Lawrie & Co. Ltd. 21, Netaji Subhas Road, Kolkata-700001, for the job captioned at the premises referred in above subject. Bids from non- registered vendors shall not be opened.

1.2 **SCOPE OF WORK**

The complete scope of work and Technical Specifications has defined in **Annexure – I**

1.3 **COMPLETION PERIOD**

Time is the essence of the order. The time schedule for completion according to the contract/ order shall be **18 (Eighteen) days** from the date of placement of order/ LOI whichever is earlier

1.4 **MANDATORY CRITERIA**

Bidders have to be enlisted with Balmer Lawrie & Co. Ltd.

1.5 **TENDER DOCUMENTS**

The vendors would be required to submit these papers (**Page No – 1 to 5**) documents along with PRICE BID - **Annex-I (Page No – 6 to 9)**. All the hardcopies of the Bid Documents as explained above and also defined in clause no. 2.0 of Condition of Contract under sealed envelope should reach at Administration Department, Ground Floor, Balmer Lawrie & Co. Ltd, 21, N S Road, Kolkata - 700001 on or before the due date of submission of tender. The Bidders who are submitting the Bids in person are requested to drop the same in our tender box located at the ground floor.

CONDITIONS OF CONTRACT

2.0 **GENERAL**

The intending tenderers shall be deemed to have visited the site and familiarized themselves thoroughly with the site conditions before submitting the tender. Non-familiarity with the site conditions will not be considered reason either for extra claims or for not carrying out the work in strict conformity with the specifications. Jr. Officer (Civil) – Administration may be contacted during office hours (Monday to Saturday 9.30AM to 6.30PM) to organize the site visit.

2.1 TAXES & DUTIES

All the taxes as applicable shall be paid extra.

2.2 NON-CONFORMANCE

Tenders not conforming to the all above mentioned requirements are liable to be rejected.

2.3 VALIDITY OF OFFER

Tendered shall keep their offer valid for a period of 60 days from the date of opening of Unpriced bid.

2.4 RATES AND OTHER ENTRIES

- (a) The tenderer should quote for all items in the Schedule of Rates.
- (b) The rates should be quoted in the same units as mentioned in the tender schedule of quantities.
- (d) Every page of the tender document including annexure / enclosures shall be stamped and signed by the tenderer or his authorized representative thereby indicating that each and every page has been read and the points noted.

2.5 RIGHT TO ACCEPT OR REJECT TENDER

- a. M/s Balmer Lawrie & Co Ltd reserves the right to accept or reject any or every tender without assigning any reason whatsoever / or to negotiate with the tenderer in the manner it considers suitable. In the event of receipt of lowest price from more than one (1) bidder, fresh price bids shall be invited from the lowest bidders only to determine final lowest bidder for placement of order.
- b. Bids of any tenderer may be rejected if a conflict of interest between the bidder and Company (Balmer Lawrie) is detected at any stage.
- d. Tender if submitted through e-mail or fax shall be summarily rejected.

2.6 Safety Rules

All the safety rules laid down by Balmer Lawrie, needs to be adhered at your own cost. This will mainly include all kinds of applicable personal protective equipment & complied tools. In case of violating any safety rules or in case of performing any unsafe acts during the execution of the job shall be stopped and the same may be undertaken by other vendor/s at your cost and risks. The detailed safety rules are as follows –

- a) Safety helmets and shoes are mandatory during the entire work for all workers and site supervisors
- b) Safety harness with full body harness for work above 6 feet of height
- c) All portable electrical tools need to be plastic body and double body insulation. No temporary joints in electrical cables are allowed. Proper plug sockets to be used while drawing power from source.
- d) While scrapping old paints, chipping out of plaster nose masks, safety goggles are must to be used

2.7 Testing & Inspection

The material, design and workmanship shall satisfy the relevant Indian & international Standards, the job specifications contained herein and codes referred to. Where the job specifications stipulate requirements in addition to those contained in the standard codes and specifications, these additional requirements shall also be satisfied. In the absence of any standards/specifications / code(s) of practice for any part of the work covered in this tender, the instructions/directions of Engineer-In-Charge will be binding on the **Supplier**.

2.8 Performance Guarantee

The supplier shall guarantee the work done and any fittings designed, manufactured, supplied, erected and tested by him against defective materials, poor workmanship, improper design, operation inadequacies & problems and failure from normal usage, for a period of 12 (twelve) calendar months after final acceptance of the work by the Owner.

2.9 Delay Penalty

Time is the essence of the order. The time schedule for completion according to the contract/order shall be **18 (Eighteen) days** from the date of placement of order/LOI whichever is earlier. In case of failing on completion of the job within time, a sum equivalent to 1% of certified bill value for each week shall be deducted which is subjected to 5% maximum.

2.10 Terms of Payment

No mobilization advance shall be paid to the contractor.

100% of the bill value will be payable by the Owner after submission of Bill accompanied by the relevant documents duly certified by Engineer-in-Charge after 30 days from the date of submission of the bill.

10% of the above bill shall be deducted towards retention money which will be released after completion and acceptance of work for performance maintenance period, which shall be twelve (12) months from the date of issue of completion certificate by the Engineer-in-Charge.

For extra items, rates shall be derived from similar item rates included in the schedule of work. Where there is no such similar item available in the schedule, rate shall be analyzed as follows:

Rate for extra item = Cost of material (a) + cost of labor inclusive of all necessary tools, tackles, equipment, machinery and consumable (b) required to carry out the work + 15% of (a+b) towards profit and overhead + taxes, duties etc.

For any Technical clarifications / queries Tenderers are requested to contact **Jr. Officer (Civil) - Admin (e-mail: chatterjee.r@balmerlawrie.com)** (from 10.00AM to 06.00PM, Monday - Friday).

For Balmer Lawrie & Co Ltd



Dilip Kumar Das
Head (Admin & CSR)

FORM OF TENDER
[TO BE FILLED IN BY THE TENDERER]
NIT No – 07/2018-19, Dated – 22.06.2018
DUE ON 26.06.2018 BY 3.00 PM

Date - 22/06/2018

To,
HEAD [Admin & CSR]
Balmer Lawrie & Co. Ltd.
21, Netaji Subhas Road
Kolkata – 700 001.

Dear Sir,

Sub. - Tender for “Construction of Waste Disposal Room” At Head Office, 21 N S Road, Kolkata- 700 001
Tender Ref: Admin/12, No. 07/2018-19, dated 22.06.2018

Having examined the subject Tender Documents consisting of Notice Inviting Tender, General Conditions of Contract, Special Condition of Contract, Price Schedule and having understood the provisions of the said Tender Document and having thoroughly studied the requirements of Balmer Lawrie & Co. Ltd. to the work tendered for in connection with the above subject job. I/We hereby submit our tender offer for the performance of proposed work in accordance with the terms and conditions as mentioned in the Tender Document at the rate[s] quoted by me/us in the accompanying price schedule based on the Schedule of Works included within the Tender document.

If the work or any part thereof is awarded to me/us, I/We undertake to perform the work in accordance with the Tender Document and accept the terms and conditions of the Tender as will be laid down therein failing which Balmer Lawrie & Co. Ltd. Shall be at liberty, without further reference to me / us and without prejudice to any of its rights or remedies, to terminate the agreement and / or to forfeit the earnest money deposited in terms thereof.

Thanking you,

Yours faithfully,

[Name & Address of Firm):- _____


Contact No. :- _____

Contact Person _____

With Designation: - _____

Technical Specifications

ANNEXURE-I



बामर लॉरी एण्ड कं. लिमिटेड
(भारत सरकार का एक प्रविष्टान्त)
Balmer Lawrie & Co. Ltd.
(A Government of India Enterprise)

Balmer Lawrie & Co Ltd
(A Government of India Enterprise)
Administration Department
21, Netaji Subhas Road
Kolkata - 700 001.

TENDER

FOR

"Construction of Waste Disposal Room"

At

Head Office, 21, N S Road, Kolkata – 700 001

TENDER REFERENCE – ADMIN/12

TENDER NO: - 07/2018-2019 DATED 22.06.2018

DUE ON 26.06.2018 BY 3.00 PM

General Conditions:

1. Details of the items under this Schedule shall be read in conjunction with the corresponding Specifications and other Tender Documents.
2. The work shall be carried out as per approved drawings, Specifications and the description of the items in this Schedule and/or Engineer's instructions.
3. Items of work provided in this Schedule but not covered in the Specifications shall be executed strictly as per instructions of the Engineer-In-Charge.
4. Unless specifically mentioned otherwise in the Contract, the Tenderer shall quote for the finished items and shall provide for the complete cost towards power, fuel, tools, tackles, equipment, Constructional Plant, Temporary Work, labour, materials, levies, taxes, transport, layout, repairs, rectification, maintenance till handing over, supervisions, colonies, shops, establishments, services, temporary roads, revenue expenses, contingencies, overheads, profits and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work according to the contract.
5. The Quantities of the various items mentioned in the Schedule of Items are approximate and may vary up to any extent or be deleted altogether, but should not exceed 15% of the BOQ. The Contractor, in his own interest, should get an indication of the probable extent of the work to be executed under any particular item in this Schedule before undertaking any preliminary and enabling work or purchasing bought out components related to the work.
6. Engineer's decision shall be final and binding on the Contractor regarding clarification of items in this Schedule with respect to the other sections of the Contract.
7. For extra items, rates shall be derived from similar item rates included in the schedule of work. Where there is no such similar item available in the schedule, rate shall be analyzed as follows:
Rate for extra item = Cost of material (a) + cost of labour inclusive of all necessary tools, tackles, equipment, machinery and consumable (b) required to carry out the work + 15% of (a+b) towards profit and overhead + taxes, duties etc. as applicable.

SCHEDULE OF WORK

NIT No – 07/2018-19, Dated – 22.06.2018

DUE ON 26.06.2018 BY 3.00 PM

Sl. No.	Description	Unit	Quantity	Rate	Amount
1	Dismantling of old 125mm thick brick wall 250mm x 250mm pillars laid in cement mortar including complete disposal of dismantled materials to the nearest municipality dumping area job all complete up to the satisfaction of the Engineer-in-charge	Sq M	20		
2	Dismantling of MS structure made of 100mm channel sections and 2.5"/3" diameter GI pipes by means of cutting manually or with the help of gas cutting system job all complete up to the satisfaction of the Engineer-in-charge and storage of dismantled items at the location within BL premises as per the instruction Note: Participants of this tender are strictly instructed to visit the site before quoting this item	LS	1		
3	Providing and laying Plain Cement concrete for foundation bolt (size - 16mmX200mm) grouting with cement mortar (1:1.5:3) including necessary shuttering & other arrangements including labour Charges for concrete cutting for column foundation holes including cleaning of rubbish and others for hole Size - 150mmX150mmX200mm The Job should be carried out up to the satisfaction of the Engineer-in-charge	Per Nos	2		
4	Supply, fabrication, erection, alignment and fixing in position true line and level. Structural steel work for lean too shed, columns/post, bracing, brackets, base plates, holding down bolts etc. made out rolled steel angles (75mmX75mmX8mm) & 12 mm thick plates or 150mm channels etc. including splicing, cutting, bending, drilling, welding & bolting etc. Preparation of bearing surface of column & post Caps/bases etc. to achieve perfect bearing with all tools & tackles and machinery all complete with two coats of Synthetic enamel painting over a coat of red oxide primer. Columns/Post- 12ft [65 mm X 65 mm X 8mm] Rafter/Bracing-50 mm X 50 mm X 8 mm angle Purlins- 50 mm X 50 mm X 8 mm angle Plate-12mm thick The Job should be carried out up to the satisfaction of the Engineer-in-charge	KG	250		
5	Providing and fixing in position 0.45mm thick pre-coated galvanised sheet (TATA BlueScope Steel Ltd./JSW Steel Ltd./ Bhushan Steel Ltd.) of required shades for roof/side cladding to be fixed with 8 mm dia nut-bolt with washer and 'J' type hook with washer onto the frame structure with all necessary cutting/bending/welding job all complete with materials, labour, scaffolding and all necessary tools as per the satisfaction of the Engineer-in-charge	Sq M	12		

Sl. No.	Description	Unit	Quantity	Rate	Amount
6	Providing and fitting 200mm dia half ground GI valley gutter made with 22 gauge GI sheet including necessary nut bolt, bitumen washer & salimar tar pudding complete with labour & materials	Meter	3.5		
7	Providing and laying 250mm thick brick masonry wall (Height - 3.5 Meters) and 375mm x 375 mm pillars with common burnt clay F.P.S. modular bricks of class designation 7.5 in superstructure in with cement mortar 1:4 (1 cement : 4 coarse sand) including the cost of all materials, labor charges and scaffoldings, job all complete up to the satisfaction of the engineer-in-charge	Cu M	5		
8	Providing, supplying and fixing 8/10 mm thick good quality glossy wall tiles (450 mm x 300 mm interior/exterior) on inner & outer walls with required highlighters including necessary backing sand cement mortar (1 cement : 4 sand), filling joints with white cement and matching pigments etc. The job shall be completed and the tiles shall be selected up to the satisfaction of the engineer-in-charge	Sq M	45		
9	Providing and laying in position 2"/2.5" thick cement concrete of mix 1:2:4 [1 Cement: 2 coarse sand: 4 graded stone aggregate (12mm to 16mm down nominal size)] at floor level (ground floor) finished with neat cement punning (Area - 7.5 Sq M) after proper ground preparation by means of sand/rubbish filling and ramming, job all complete by works (maintaining proper slope), all materials, labour charges, minimum ten days curing from the completion of the concreting work. The job should be carried out up to the satisfaction of the engineer-in-charge	Cu M	2		
10	Providing and fixing MS wire mess of opening size 2"x 2" and required MS Angel of size 25 mm x 25 mm for frame structure job all complete with cutting, bending, welding, two coats of synthetic enamel primer and two coats of synthetic enamel paint The job should be carried out up to the satisfaction of the engineer-in-charge	Sq M	3.5		
11	Providing and fixing MS door of size 1200 mm x 2100 mm with 25mm x 25mm x 5mm thick MS angel for frame and 2mm thick MS Sheet for Panel cover with all necessary fittings like hinges, hash bolt (one side) etc. finished with one/two coats of primer paint and two coats of synthetic enamel paint The job should be carried out up to the satisfaction of the engineer-in-charge	KG	25		
				TOTAL =	