

PART - II (PRICED) SCHEDULE OF WORK

Tender No. MMLH/AC/PT/24

A) Design, manufacturing, supply, lifting, shifting, installation, testing, commissioning, conducting performance guarantee test at site and handing over of VRF type A.C. systems for the EXIM Admin Block and Split Air Conditioners for other facilities of the Multi Modal Logistic Hub								
				Supply		Erection		
Sl. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total
Indoor Units - Ground Floor								
1	EDI Room	1 TR Cassette	1					
2	Appraisers Cabin	0.8 TR Cassette	1					
3	Examining Cabin	0.8 TR Cassette	1					
4	Bank with Manager Room & Strong Room	2200 CMH, 4TR Ductable	1					
5	MMLH Office, MMLH Operations Room, Manager's Room and Cash Room	900 CMH, 2TR Ductable	2					
6	Reception cum waiting (LW)	1800 CMH, 3TR Ductable	1					
7	Staff of Customs	650 CMH, 1.2TR Ductable	1					
8	Reception cum waiting (RW)	1.5 TR Cassette	1					
9	AS Commissioner 1	0.8 TR Cassette	1					
10	AS Commissioner 2	0.8 TR Cassette	1					
11	Preventive Section with Discussion Room	850 CMH, 1.5 TR Ductable	1					
12	Supdt Cabin	0.6TR Cassette	1					
13	Customs Sepoy	1.2 TR Cassette	1					
14	Rental Office (Type 1)	0.6 TR Cassette	4					
15	Rental Office (Type 2)	0.6 TR Cassette	4					
16	Officers Dining	1400 CMH, 3 TR Ductable	1					
Outdoor Units								
1	Roof mounted, vertical discharge VRF outdoor units with all compressors inverter controlled suitable for R410a, or equivalent.	12 HP	1					
2	Roof mounted, vertical discharge VRF outdoor units with all compressors inverter controlled suitable for R410a, or equivalent.	22 HP	1					
Outdoor duty treated fresh air unit								
1	Double skin roof mounted treated fresh air unit	2600 CMH	1					
Miscellaneous items								
1	GI Ducting (120 GSM) with 19mm thick aluminium foil faced nitrile rubber insulation, supports, collar pieces, dampers etc.	26G	15M ²					
2	Aluminum Powder Coated Sq Diffuser with VCD.	Size to suit false ceiling grid	1.5M ²					
3	PVC Drain Pipe with 13mm thick aluminium foil faced nitrile rubber	25mm dia	75M					
First Floor								

PART - II (PRICED) SCHEDULE OF WORK								
Tender No. MMLH/AC/PT/24								
A) Design, manufacturing, supply, lifting, shifting, installation, testing, commissioning, conducting performance guarantee test at site and handing over of VRF type A.C. systems for the EXIM Admin Block and Split Air Conditioners for other facilities of the Multi Modal Logistic Hub								
				Supply		Erection		
SI. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total
SI. No	Room/ Area	Indoor Unit TR and Type	Qty		Unit Rate		Unit Rate	Total
Indoor Units								
1	CEO's Cabin with Ante Room	1.2 TR Cassette	1					
		0.6 TR Cassette	2					
2	COO's Cabin	1.2 TR Cassette	1					
3	Discussion's room	1 TR Cassette	1					
4	MMLH Work Stn. with Surveillance Room	1500 CMH, 3 TR Ductable	1					
		1300 CMH, 2.5 TR Ductable	1					
5	Rental Office 1 – 3 nos.	0.8 TR Cassette	3					
		0.6 TR Cassette	3					
6	Rental Office 2 – 2 nos.	0.6 TR Cassette	4					
7	Rental Office 3 – 2 nos.	0.6 TR Cassette	4					
8	Rental Office 4 – 4nos.	0.6 TR Cassette	8					
9	Operational Room	1.2 TR Cassette	1					
10	Conference cum training Hall	1800 CMH, 4.5 TR Ductable	2					
11	CFO's Cabin	1 TR Cassette	1					
Outdoor Units								
1	Roof mounted, vertical discharge VRF outdoor units with all compressors inverter controlled suitable for R410a, or equivalent.	22 HP	2					
Outdoor duty treated fresh air unit								
1	Double skin roof mounted treated fresh air unit	3600 CMH	1					
Miscellaneous items								
1	GI Ducting (120 GSM) with 19mm thick aluminium foil faced nitrile rubber insulation, supports, collar pieces, dampers etc.	26G	15M ²					
2	Aluminum Powder Coated Sq Diffuser with VCD.	Size to suit false ceiling grid	1M ²					
3	PVC Drain Pipe with 13mm thick aluminium foil faced nitrile rubber	25mm dia	75M					
B) Supply and Installation of Split Type AC for Admin - Domestic Building								
SI. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total

PART - II (PRICED) SCHEDULE OF WORK

Tender No. MMLH/AC/PT/24

A) Design, manufacturing, supply, lifting, shifting, installation, testing, commissioning, conducting performance guarantee test at site and handing over of VRF type A.C. systems for the EXIM Admin Block and Split Air Conditioners for other facilities of the Multi Modal Logistic Hub								
Sl. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Supply		Erection		Total
				Unit Rate	Amount	Unit Rate	Amount	
1	Cabin 1 - Size: 3.5m x 3.175m x 3m	Supply and Installation of 1 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
2	Cabin 2 Size: 3.5m x 2.635m x 3m	Supply and Installation of 1 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
3	Cabin 4 Size: 3.5m x 2.635m x 3m	Supply and Installation of 1 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
4	Discussion's room Size: 6m x 3.175m x 3m	Supply and Installation of 1.5 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
5	Cash counter Size: 4.435m x 3.175m x 3m	Supply and Installation of 1.5 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					

PART - II (PRICED) SCHEDULE OF WORK

Tender No. MMLH/AC/PT/24

A) Design, manufacturing, supply, lifting, shifting, installation, testing, commissioning, conducting performance guarantee test at site and handing over of VRF type A.C. systems for the EXIM Admin Block and Split Air Conditioners for other facilities of the Multi Modal Logistic Hub								
				Supply		Erection		
Sl. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total
6	Work stations Size: 10.21m x 3.175m x 3.9m	Supply and Installation of 2 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	2					
7	Reception Size: 6.5m x 2.3m x 3.9m	Supply and Installation of 2 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
C) Supply and Installation of Split Type AC for Office building for Temperature Controlled Warehouse								
				Supply		Installation		
Sl. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total
1	Work Stations	Supply and Installation of 1.5 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	2					
2	Discussion Room	Supply and Installation of 1.5 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					

PART - II (PRICED) SCHEDULE OF WORK								
Tender No. MMLH/AC/PT/24								
A) Design, manufacturing, supply, lifting, shifting, installation, testing, commissioning, conducting performance guarantee test at site and handing over of VRF type A.C. systems for the EXIM Admin Block and Split Air Conditioners for other facilities of the Multi Modal Logistic Hub								
				Supply		Erection		
Sl. No	Room/ Area	Indoor Unit TR and Type / Split AC	Qty	Unit Rate	Amount	Unit Rate	Amount	Total
3	Manager Room	Supply and Installation of 1.5 TR 5 star split type air conditioner with R22 refrigerant and all necessary piping and accessories, voltage stabilizer and remote control.	1					
D	Total Basic Supply (A+B+C)							
	Applicable IGST (%Bidder to Indicate)							
	Applicable SGST (%Bidder to Indicate)							
	Applicable CGST (%Bidder to Indicate)							
E	Grant Total of Supply inclusive of GST							
F	Total Basic Erection (A+B+C)							
	Applicable IGST (%Bidder to Indicate)							
	Applicable SGST (%Bidder to Indicate)							
	Applicable CGST (%Bidder to Indicate)							
G	Grant Total of Erection inclusive of GST							
H	Grant Total Basic (D+F)							
I	Grand Total inclusive of GST							
J	Total Amount in Word							
Note : 1.All supply price shall be inclusive of transportation and transit insurance 2. If any rate not quoted by bidder same shall be considered as included in other items and no extra amount shall be paid by Owner 3. All Erection Installation price shall be inclusive of any civil, structural, anchor-fastening work required to lay ducting, install indoor and outdoor units								
Signature and Seal of Bidder								